


17-8-26W
CSW

17-8-26W
KANSAS

DREILING OIL, INC.

Victoria, Kansas 67671



API# 15-179-20353

WELL LOG

Dreiling Oil, Inc.
Rt. #2
Company Victoria, Kansas 67671

Farm Kysar No. 2

Total Depth 3,875'

Comm. 6-4-73 Comp. 6-22-73

Contractor Dreiling Oil, Inc.
Rt. #2
Victoria, Kansas 67671

Sec. 17 Twp. 8 Rng. 26

Location C SW/4

County Sheridan

Elevation: 2441 K. B.
2438 D. F.
2436 G. R.

Casing Record

166' - 8 5/8"
3,874' - 4 1/2"

Cement Record

165 sacks cement
cemented w/20 bbl. fresh water
& 200 gal. B.J. Flush & 50 sks
Poz Mix 2% Gel & 12# Gilsnite per sk
17 1/2 sks common 12% salt
Figures indicate Bottom of Formations

Production:

0'	35'	Sand
35'	65'	Gray Shale
65'	166'	Blue Shale
166'	1315'	Shale
1315'	1704'	Shale & Gyp
1704'	1873'	Sand
1873'	1930'	Red Bed & Shale
1930'	2088'	Shale
2088'	2123'	Anhydrite
2123'	2925'	Shale
2925'	3217'	Shale & Lime
3218'	3600'	Shale
3600'	3875'	Lime
3875'	T.D.	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)



I, Joe Hess, Secretary Treasurer of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Kysar #2.

LOG TOPS:

SC	2084
HOW	3270
TOP	3360
HEEB	3580
TOR	3602
LANS	3620
BKC	3836
TD	3875

Joe Hess
JOE HESS

this 29th day of June, 1973.



Cecilia Basgall
Cecilia Basgall Notary Public