

DREILING OIL, INC.

Victoria, Kansas 67671

API# 15-179-20,362

WELL LOG

Dreiling Oil, Inc.
Rt. #2
Company Victoria, Kansas 67671

Farm Kysar No. 3

Total Depth 3,879'

Comm. 8-28-73 Comp. 9-6-73

Contractor Dreiling Oil, Inc.
Rt. #2
Victoria, Kansas 67671

Sec. 17 Twp. 8 Rng. 26W

Location C NW SW

County Sheridan

Elevation: 2467 K. B.

2464 D. F.

2462 G. R.

Casing Record

169' - 8 5/8
4 1/2" - 3,875'

Cement Record

125 sacks cement
cemented w/20 bbls fresh water
& 20 bbl. salt flush. Cemented
w/50 sks of 50/50 Pos Mix-2% Gel
& 12 1/2 lbs Gilsomite per sk. 175 sks common w/10% salt.

Production: OIL

0'	50'	Sand
50'	169'	Blue Shale
169'	590'	Shale
590'	1570'	Shale
1570'	1730'	Shale
1730'	1930'	Sand
1930'	2122'	Shale & Red Bed
2122'	2153'	Anhydrite
2153'	2617'	Shale
2617'	2870'	Shale & Lime
2870'	3080'	Lime & Shale
3080'	3410'	Lime
3410'	3647'	Lime & Shale
3647'	3780'	Lime
3780'	3817'	Shale & Lime
3817'	3866'	Lime
3866'	3879'	Shale
3879'	T.D.	

STATE OF KANSAS)
(ss
COUNTY OF ELLIS)

Log Tops
top 3388
heeb 3601
tor 3624
lkc 3641
ltd 3879
rtd 3879

I, Joe Hess, Secretary Treasurer, of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the Kysar #3.

JOE HESS

Subscribed and sworn to before me this 12th day of September, 1973.



Cecilia Basgall
Cecilia Basgall Notary Public

