

33-8-27W

15-179-20104

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY MARMIK OIL & ABERCROMBIE DRILLING

SEC. 33 T. 8 R. 27W
LOC. C SW SW

FARM Mosier

NO. 1

TOTAL DEPTH 3125'

COMM. 5-22-68

COMP. 5-25-68


SHOT OR TREATED

CONTRACTOR Abercrombie Drilling

ISSUED 9-14-68

COUNTY Sheridan

KANSAS



CASING

20	10
15	XX 7" 253' cem w/ 125 ex
12	6
13	5

ELEVATION 2583' KB

PRODUCTION DRY/NEVA

0	70	Sand
70	1250	Shale
1250	1370	Sand
1370	1800	Shale
1800	1995	Sand
1995	2211	Red Shale
2211	2246	Anhydrite
2246	2460	Shale
2460	2650	Lime & Shale
2650	2855	Shale & Lime
2855	3125	Lime & Shale
3125		Rotary Total Depth

Drill 255' of 9" surface hole and set 7" csg. @253' w/125 ex. Sunset cement.
Cement circulated. Plug was down @1:15 p.m., 5-22-68.
Dry & Abandoned.

ELECTRIC LOG TOPS

ELEVATION

Anhydrite	2207	(+ 376)	2583 K. B.
B/Anhy.	2241	(+ 342)	2581 D. F.
B/Ft. Riley	2774	(- 191)	2575 G. L.
Cottonwood	3034	(- 451)	
Neva	3083	(- 500)	
E.L.T.D.	3119	(- 536)	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

A. L. Abercrombie, Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the #1 MOSIER, SW SW, Section 33-8-27W, Sheridan County, Kansas.

A. L. Abercrombie
A. L. Abercrombie, President