

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-179-00172

Company- **HEATHMAN-SEELIGSON DRIG.**
 Farm- **Brown "D"** No. **1**

SEC. **36** T. **8** R. **27W**
 NW SE SW

Total Depth. **4111'**
 Comm. **5-17-56** Comp. **5-28-56**
 Shot or Treated.
 Contractor. **Heathman & Seeligson Drig.**
 Issued. **6-30-56**

County **Sheridan**
KANSAS



CASING:
8 5/8" 294.88' cem w/175 sx

Elevation. **2656' DF**

Production. **Dry**

Figures indicate Bottom of Formations.

clay & sand	40
shale & shells	130
sand	260
shale & shells	1200
shale & sand	1415
shale	1596
shale & shells	1755
blain anhydrite	1790
shale & red bed	2271
anhydrite	2310
shale & shells	2356
shale	2530
shale & shells	2825
shale & lime	3300
lime	3395
shale & lime	3851
lime	4085
lime & shale	4111 RTD
Total Depth	

Tops:
 Heebner 3792
 Toronto 3818
 Lansing 3832
 Base Kansas City 4054

DST #1 3865-80', open 35 min., rec. 10'
 mud. BHP 1310#.

DST #2 3888-3912' open 30 min, no blow
 Rec. 1' mud w/very few oil specks. IFP O#
 FFP O#, BHP O#.

DST #3 3983-4010', open 30 min., no blow,
 rec. 4' mud. BHP 1030#.

OKC 4054
 2656
 -1398
 832
 656
 176