

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Bldg. Wichita, Kansas

10-8-29W

15-179-00004

Company STANOLIND OIL & GAS CO.
Farm C.L.Thompson No. 1

SEC. 10 T. 8 R. 29 W
NW 1/4 SE

Total Depth. 4745'

Comm. 10-25-46


Comp. 11-23-46

Shot or Treated.

Contractor.

issued. 12-21-46

County. Sheridan
KANSAS



CASING:

13 3/8"

150' Cem.

Elevation. 2800. set 4 rh

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	0-9	Tops:	
shaley coarse gravel	152	Lansing	3885
shale & shells	410	Mississippi	4547
shale, shells & sand	940	Arbuckle	4694
shale & shells	1575		
shale & sand	1970		
shale & redbeds	2370		
shale & shells	2535		
lime - anhydrite	2590		
red beds	2700		
shale	2755		
shale & sand	2865		
red bed & shells	2955		
lime & shale	3017		
sand & lime	3069		
red beds & sand	3165		
lime & shale	3242		
lime	3293		
lime & sdy shale	3350		
lime	3353		
lime sdy	3359		
shale	3387		
lime	3432		
shale & lime	3466		
shale	3482		
lime & shale	3610		
shale	3678		
shale & lime	3735		
lime brkn	3815		
lime	4242		
lime brkn	4282		
shale & sand	4318		
shale & lime	4340		
lime	4376		
shale & lime	4401		
lime lgt gy, fine	4403		
xlyn - Core #1 1 1/2' Rec.			
lime	4406		
shale & lime	4499		
lime	4501		

Core #2 - no. Rec.
(Small piece sand, no
oil show)
shale & lime - drld. 4566
lime & chert 4585
lime 4604
lime & chert 4617
lime 4712
lime - tan, fine xlyn, 4715
dolomite, good por.
Core #3 - 2' Rec.
Halliburton test run
rec. 120' mud 660' wtr.
open 15 min.
lime - drilled 4745
Ran Schlumberger Survey
Total Depth.