

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

26-8-29W

COMPANY LEO J. DREILING

SEC. 26 T. 8 R. 29W

FARM Selbe

NO. 1

LOC. C SW SW

15-179-20040

COUNTY Sheridan

TOTAL DEPTH 4151'

COMM. 9-2-67

COMP. 9-10-67

SHOT OR TREATED

CONTRACTOR L. J. Dreiling

ISSUED 12-267

12-2-67

CASING

20

10

15

8 5/8" 200' cem w/ 150 SX

12

6

13

5

ELEVATION 2792' KB

PRODUCTION DRY/BKC

FIGURES INDICATE BOTTOM OF FORMATIONS

0'	40'	Top Soil	
40'	120'	Sand & Clay	
120'	160'	Clay	
160'	200'	Shale	
200'	280'	Shale	
280'	1080'	Shale	
1080'	1840'	Shale	
1840'	1990'	Shale	
1990'	2080'	Shale & Bent Streaks	
2080'	2110'	Sand	
2110'	2391'	Shale & Red Bed	
2391'	2425'	Anhy.	
2425'	2442'	Anhy.	
2442'	2700'	Shale & Shells	
2700'	2931'	Shale & Lime Streaks	
2931'	3080'	Lime	
3080'	3240'	Shale & Lime	
3240'	3386'	Shale & Lime	
3386'	3475'	Lime	
3475'	3635'	Lime & Shale	
3635'	3720'	Lime & Shale	
3720'	3850'	Lime	
3850'	3900'	Lime	TOPS: SMP
3900'	3950'	Lime	Anhydrite 2391
3950'	3960'	Lime	Topeka 3655
3960'	4030'	Lime	Heebner 3864
4030'	4115'	Lime	Toronto 3887
4015'	4151'	Lime	Lansing 3900
4151'	T.D.	Lime	Base Kansas
			City 4142

STATE OF KANSAS)

)ss

COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Selbe #1.

Leo F. Dreiling