

KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

35-8-29W

COMPANY **ROCK ISLAND O & R**


SEC. ~~303~~ **8** N. 29W
 LOC. **NW NE SW**

FARM **Pratt** NO. **2**

15-179-20069
Sheridan

TOTAL DEPTH **4225'**
 COMM. **1-25-68** COMP. **2-4-68**
 SHOT OR TREATED
 CONTRACTOR **Red Tiger Drlg.**
 ISSUED **4-6-68**

COUNTY



CASING
 20 10
 15 8 5/8" 221' cem w/ 180 sx
 12 6
 13 5
 4 1/2" 4224' cem w/ 50 sx

ELEVATION **2819' KB**

PRODUCTION **103 BOPD, NW**
Lans 3998-4108

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Shale	0	136
Shale	136	146
Sand	146	198
Shale	198	222
Shale & Sand	222	500
Shale	500	1755
Sand & Shale	1755	1880
Shale & Shells	1880	2437
Anhydrite (Top)	2437	2460
Anhydrite (Base)	2460	2474
Shale & Shells	2474	2980
Shale & Lime	2980	3405
Lime	3405	3475
Lime & Shale	3475	3645
Lime	3645	3710
Lime & Shale	3710	3864
Lime	3864	4225

TOPS: LOG

Anhydrite	2436
Base Anhydrite	2474
Heebner	3841
Toronto	3912
Lansing	3926
Base Kansas	
City	4156
RTD	4225

I certify that this a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Maxine V. Starr
 Maxine V. Starr

Subscribed and sworn to before me this 6th day of February, 1968.

Betty M. Embury
 Notary Public