



## Operator

DONALD C. SLAWSON

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:

Well No.	1	Lease Name	Currier 'D' (OWDD)	Dry Hole
S 14 T 8 R 30W E W				
<b>WELL LOG</b> Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 4298 Washdown 4298 - 4320 Lime 4320 - 4385 Shale & Lime 4385 - 4445 Lime & Shale 4445 - 4481 Lime 4481 - 4589 Lime & Shale 4589 - 4620 Shale & Lime 4620 RTD			LOG TOPS ANH 2582 (+33) B/ANH 2616 (+299) HEEB 3981 (-1066) LANS 4018 (-1103) STK 4207 (-1292) B/KC 4258 (-1343) MARM 4287 (-1372) PAW 4375 (-1460) MYR STA 4428 -1513) U/CHER 4445 (-1530) FT SC 4454 (-1539) L/CHER 4479 (-1564) CONG 4553 (-1638) MISS (OSAGE) 4568 (-1653) LTD 4620 (-1705)	
DST #1 4342-4385 (PAW) 30-30-30-30, VWB/20", Rec. 20' M w/spts of C., IFP 48-48#, ISIP 79#, FFP 48-48#, FSIP 63#. DST #2 4400-4445 (MYR STA) 30-30-30-30, VWB/28", Rec. 20' M, NS. IFP 16-16#, ISIP 37#, FFP 16-16#, FSIP 32#. RTD - 4620' - PD 11:00 P.M.				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

  
Signature

Title

Date

8hLLS

14-8-30W

WELL LOG

OPERATOR: Donald C. Slawson  
200 Douglas Building  
Wichita, Kansas 67202

LEASE: #1 Currier 'D' - OWDD  
NE NE NW of Sec. 14-8-30W  
Sheridan County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
200 Douglas Building  
Wichita, Kansas 67202

COMMENCED: October 16, 1978

COMPLETED: October 20, 1978

CASING: Old Info: Surface - 8 5/8" @ 290' w/170 sx  
New Info: Cement 1-30', no 2nd plug @ 325',  
no bottom plug @ 1675'

0 - 4298 Washdown  
4298 - 4320 Lime  
4320 - 4385 Shale & Lime  
4385 - 4445 Lime & Shale  
4445 - 4481 Lime  
4481 - 4589 Lime & Shale  
4589 - 4620 Shale & Lime  
4620 RTD

STATE OF KANSAS )  
 ) SS.  
COUNTY OF SEDGWICK )

I, R.J. Thatcher, of the Slawson Drilling Company, Inc. upon oath  
state that the above and foregoing is a true and correct copy of the log  
of the #1 Currier 'D' (OWDD) test.

  
R. J. THATCHER, Engineer

Subscribed and sworn to before me this 16th day of January, 1979.