

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

36-8-32W


15-193-00003

Company- GENERAL CRUDE OIL COMPANY
Farm- C.J. Bremenkamp No. 1

SEC. 36 T. 8 R. 32W
C NE SW

Total Depth. 5305'
Comm. 9-5-58 Comp. 9-24-58
Shot or Treated.
Contractor. Badger Drillers, Incorporated.
Issued. 11-22-58

County Thomas
KANSAS



CASING:
8 5/8" @ 424' w/300 sx.

Elevation. 3061'

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	40
sand & shale	290
shale	320
blue shale	424
shale	1000
shale & shells	1580
sand	1820
sand & lime streaks	1980
sand & shale	2295
sand & anhydrite	2355
red bed & shale	2532
shale	2670
lime & shale	2935
red bed & shale	3100
shale & dolomite	3230
shale & shell	3350
shale & lime	3505
lime	3568
lime & shale streaks	3603
lime & sdy shale	3662
lime	3725
shale & lime	3825
lime	4078
lime & shale	4143
lime	4628
chert	4663
lime & chert	4820
chert	4844
lime	4860
lime & chert	4880
lime	4965
Viola (Dolomite)	4985
lime	5259
lime & sand	5305 RTD
Total Depth	

TOPS:

Dakota	1508
Nava (Scout)	3420
Wabaunsee (Scout)	3630
Topeka	3842
Heebner	4042
Lansing	4081
Marmaton	4422
Morrow Zone (Scout)	4590
Mississippi (Scout)	4645
Kinderhook (Scout)	4810
Arbuckle	4968
Reagan	5262