

7-8-36W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-193-30019

Company- MORRISON PRODUCING CO.
Farm- Fulwider No. 1

SEC. 7 T. 8 R. 36W
C NE NE

Total Depth. 4971'
Comm. 4-17-62 Comp. 5-1-62
Shot or Treated. no
Contractor. Murfin Drilling Co.
Issued. 9-1-62

County Thomas
KANSAS



Elevation. 3392' KB

CASING:

8 5/8" 314' cem w/250 sx.

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	110
sand	235
shale	1695
sand-shale	2290
shale & lime streaks	2400
gyp	2410
shale gyp	2690
gyp-shale	2745
red bed-sand-shale	2920
anhydrite	2954
shale-shells	3000
shale & gyp streaks	3025
shale	3185
shale & sand	3340
shale-lime	3400
lime-shale	3862
lime	3980
lime & chalk	4080
lime	4700
lime & shale	4763
lime & sand	4879
lime	4955
Mississippi	4965
Mississippi	4971 RTD
Total Depth	

DST #6 4730-4775' op 1 hr, Rec. 100'
muddy water. IF 60# FF 97# IBHP 1500#/
20 min. FBHP 1311#/20 min.

DST #7 4920-4965' op 1 hr, Rec. 25'
mud. IF 35# FF 50# IBHP 1197#/20 min.
FBHP 970#/20 min.

TOPS: ELECTRIC LOG

Wabunsee	3734
Heebner	4144
Toronto	4174
Lansing Kansas City	4190
Base Kansas City	4500
Sand	4856
Mississippi	4859

DST #2 3818-3862' op 1 hr, Rec. 5' mud
w/oil specks. IF 0# FF 0# IBHP 1122#/
20 min. FBHP 224#/20 min. Weak blow 3 min.

DST #3 4149-4186' op 45 min, Rec. 5'
muddy water w/few specks oil. IF 37#
FF 37# IBHP 784#/20 min. FBHP 75#/20 min.

DST #4 4190-4232' op 45 min, Rec. 30'
watery mud. IF 37# FF 52# IBHP 1273#/
20 min. FBHP 1159#/20 min.

TOPS: SAMPLE

Blaine	2605
Cimarron-Anhydrite	2920

DST #5 4240-4256' op 2 hrs, Rec. 300'
salt water. IF 37# FF 149# IBHP 1311#/
20 min. FBHP 1177#/20 min.

DST #1 1768-1788' op 15 min, Rec. 75'
mud & water. IF 15# FF 40# IBHP 280#/15