

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15

141

20,058

County


Number

WICHITA BRANCH

S. 24 T. 8S R. 39W E

Loc. SW SW NW

County Sherman

640 Acres
N

Locate well correctly

Elev.: Gr. 3625

DF KB

Operator

Benson Mineral Group, Inc.

Address

3200 Anaconda Tower Denver, Colorado 80202

Well No.

Lease Name

1-24

Deeds

Footage Location

2310

feet from (N) X line

330

feet from (E) (W) line

Principal Contractor

Geologist

R & N Drilling

Spud Date

Date Completed

Total Depth

P.B.T.D.

7/28/79

7/29/79

1038'

Directional Deviation

Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	7 7/8"	5 1/2"		318.45'		40	
PRODUCTION	4 3/4	2 7/8"		1034.45'		20	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
None			1 SPF		933-70
TUBING RECORD					
Size	Setting depth	Packer set at			
None					

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Foam frac x 40,000# 20-40 sand x 22,000 gal 70 quality fom con- taining 52 gal Pen-5 surfactant, 2% KCl x 2#/gal 20-40 sand. Run 2,000 gal pad followed by 20,000 gal foam x 2#/gal 20-40 sand. Ran 6 Cla Sta. Flush x N ₂ .	933-70

INITIAL PRODUCTION

Date of first production SIGW 10-5-79		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas; 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Benson Mineral Group, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1-24	Lease Name Deeds		
S 24 T 8S R 39W E W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
soil shale sand shale/sand	0 8 40 402	8 40 402 1038	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	<i>Paul C. Ellison (po)</i> Signature Paul C. Ellison, Vice President Title September 18, 1981 Date		

82089