

State Geological Survey
WICHITA BRANCH
AFFIDAVIT OF COMPLETION FORM

2-8-40W. Inc 81
ACO-1 WELL HISTORY
Compt. _____

TYPE

SIDE ONE

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP _____

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F _____ Letter requesting confidentiality attached.

C 5 Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 9258 EXPIRATION DATE 12-84

OPERATOR Goodland Gas Company API NO. 15-181-20265

ADDRESS 1400 Post Oak Blvd., Suite 710 COUNTY Sherman

Houston, Texas 77056 FIELD Wildcat

** CONTACT PERSON Suzanne Parks PROD. FORMATION Niobrara
PHONE 713/ 951-0590 No _____ Indicate if new pay.

PURCHASER N/A LEASE Wolf Eyth

ADDRESS _____ WELL NO. 1-2

DRILLING Western Well Drilling, Inc. WELL LOCATION SW SW

CONTRACTOR ADDRESS _____ 330 Ft. from South Line and

ADDRESS 11299 Old Brighton Road 600 Ft. from West Line of (E)

Henderson, Colorado 80640 the SW (Qtr.) SEC 2 TWP 8S RGE 40 (W)

PLUGGING N/A WELL PLAT _____ (Office Use Only)

CONTRACTOR ADDRESS _____

ADDRESS _____

TOTAL DEPTH 1371' PBTD _____

SPUD DATE 11-10-83 DATE COMPLETED 11-17-83

ELEV: GR 3712 DF 3715 KB 3717

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE N/A

Amount of surface pipe set and cemented 343 DV Tool Used? No

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion _____ Other completion _____ NGPA filing _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

that: Suzanne Parks, being of lawful age, hereby certifies

I am the Affiant and I am familiar with the contents of the foregoing Affidavit.

State Geological Survey
WICHITA BRANCH

ACO-1 Well History

Side TWO

OPERATOR Goodland Gas Company

LEASE NAME Wolf Eyth

SEC 2 TWP 8S RGE 40

WELL NO 12

(E)
(W)

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
<input type="checkbox"/> Check if no Drill Stem Tests Run. <input type="checkbox"/> Check if samples sent Geological Survey.			Blue Shale	300'
			DIL/SFL CNL/LTD/GR CYBERLOOK CBL/VDL/GR PERF/DCL	344-1371 1000-1371 1150-1371 500-1301 1175-1301

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
<u>Frac</u> 623 BBLs 20# gel; 40 tons CO ₂ ; 49,600 lbs 20/40 sand;	
33,000 lbs 10/20 sand; 583 BBLs CO ₂ ; 20#/1000 gal gel	

Date of first production <u>Shut in</u>	Producing method (flowing, pumping, gas lift, etc.)	Gravity
Estimated Production-I.P.	Oil bbls. 200 MCF	Gas % Water % Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)		Perforations 1204-1242

Report of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Secks	Type and percent additives
Surface	9 7/8"	7"	17	343	Class "A"	85	50/50 POZ, 2% gel
Production	6 1/4"	4 1/2"	9.5	1342	Class "A"	90	10% Salt .75 % CFR2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Secks cement	Shots per ft.	Size & type	Depth interval
			2	3 1/8" Hyper	1204-1242
TUBING RECORD				JRT II	
Size	Setting depth	Pecker set at			