

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


11-8-40a
15-181-00015

Company—KINGWOOD OIL CO. & AURORA GASOLING CO.
Farm— G. W. Rauckmann No. 1

SEC. 11 T. 8 R. 40W
SE SE NE

Total Depth. 5573
Comm. 6-25-52 Comp. 8-2-52
Shot or Treated.
Contractor. J. D. Ferrell Drilling Co., Inc.
Issued. 11-15-52

County Sherman
KANSAS



CASING:

10 3/4" 3221.96' cem w/200 sx circ.

Elevation. 3707
2708 (m)

Production. dry

Figures indicate Bottom of Formations.

cellar 5
cly sandy 60
clay sdy, shale 210
water sand 295
shale 930
shale, shells 1195
lime, shale 1419
shale 1480
shale, lime, shells 1685
lime 1758
shale, shells 1840
shale, lime 1960
lime 1978
shale 2095
sand 2200
shale, sand 2226
sand, shale strks 2283
sand, shale 2507
sand, red bed 2585
shale, shells 2640
shale, sand strks 2687
anhydrite, shale 2798
shale 3040
shale, red bed 3165
shale 3169
anhydrite, shale 3208
red bed 3255
anhydrite, red bed 3407
red bed, shale 3505
red bed 3605
red bed, shale 3720
shale, lime, anhydrite 3770
red bed, shale, shells 3800
lime 3845
shale 3875
shale, lime 3885
lime 4154
lime w/oil show 4166
lime, shale w/show 4175
lime 4235
lime, shale 4280

lime 5372
chert, lime 5384
lime 5550
sand 5573
Total Depth RTD
Tops:
Topeka 4030
Heebner 4332
Lansing Kansas City 4362
Marmaton 4705
Cherokee 5051
Miss. Lime 5183
Arbuckle 5472
Regan Sand 5550

lime 4755
shale, lime, shells 4775
shale, lime 4805
lime 4860
chert, lime 4880
lime 5045
lime, sand 5061
-Cored- 5061-5075
shale, sand 5110
shale 5145
shale, lime 5173
lime, sand 5190
lime 5292
chert, lime, pyrite 5305
lime, chert 5316
lime 5333
lime, chert 6360