

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


5-9-15W

Company- ANDERSON-PRICHARD OIL COPR.
Farm- Beisner No. 1

SEC. 5 T. 9 R. 15W
15-41-00046
SW NW NE

Total Depth. 3842
Comm. 1-17-53 Comp. 1-30-53
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 2-14-53

County Osborne
KANSAS



CASING:
8 5/8" 206' cem

Elevation. 2051 BB
2048 (m)
Production. dry

Figures Indicate Bottom of Formations.

surface clay	206
shale	660
sand	780
shale	950
red bed, shale	1075
shale	1190
anhydrite	1230
shale	1475
shale, lime	2240
lime	2605
lime, shale	2765
lime	3842 RTD
Total depth	

Tops:	
Topeka	2981
Heebner	3203
Toronto	3225
Brown Lime	3249
Lansing	3259
Conglomerate	3627
Viola	3698
Simpson	3767
Arbuckle	3811

Drill Stem Test:

- #1 3211-52, open 30 min., rec.
8' mud, BHP 915#.
- #2 3210-38, open 1 hr., rec.
25' mud, BHP 135#
- #3 3252-3307, open 1 hr., rec.
30' mud (spots oil), BHP 32#.
- #4 3309-27, open 30 min., weak
blow, rec. 5' mud BHP 0.
- #5 3815-35, open 45 min., strong
blow decreasing to zero in 40
min., rec. 2650' muddy SW, BHP
1110#.