

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


Company - VICKERS PETROLEUM CO., INC.  
Farm - Gamble No. 4

SEC. 3 T. 9 R. 16W  
NW SW NW

15-103-03592

Total Depth. 3424'  
Comm. 5-20-48 Comp. 6-21-48  
Shot or Treated. Acidized  
Contractor.  
Issued. 7-24-48

County. Rooks KANSAS



Elevation. 946

Production. Est. 50 BO & 35 BWPD

CASING:  
8-5/8" 74' Cem. w/ 40 sx  
5-1/2" 3424' Cem. w/140 sx

Figures Indicate Bottom of Formations.

surface	0-74
shale	355
shale & sand	940
shale & red bed	1125
red bed & shale	1255
anhydrite	1285
shale & shells	1620
salt, shale & shells	1670
shale & lime	1940
lime brkn	2225
lime	2330
lime brkn	2395
lime	2455
shale & lime	2600
shale	2710
lime & shale	2975
lime	3005
shale & lime	3058
lime	3066
shale	3077
lime	3340
shale & some lime	3416
conglomerate	3418
dolomite	3424
Total Depth	

Lane Wells Plug @ 3391  
Ran Lane Wells Radioactivity Log  
Perforated 36 shots 3261-3276  
2000 gal. acid, test 2 bbls  
fluid per hour.  
Lane Wells Plug @ 3255' top  
Perforate 36 shots 3176-3184  
3000 gal. acid test 2 1/4 bbls fluid  
per hour 50% water.  
Perforate 36 shots 3116-3127  
Perforate 35 shots 3238-3248  
2000 gal. acid 3116-3127  
2000 gal. acid 3238-3248  
Drill out Lane Wells Plug. Put  
on pump.

Tops:  
Lansing 3075  
Base K. G. 3310  
Conglomerate Chert 3414  
Arbuckle 3416