


*Plotted per*  
**3-9-16W**

CITIES SERVICE OIL CO.  
Reese No. 2.

SEC.3 T.9 R. 16 W  
CNL NE SE  
330'S 660'W E $\frac{1}{4}$  Cor.

Total Depth. 3183-3182 SLM  
Comm. 8-18-41 Comp. 9-19-41  
Shot or Treated.  
Contractor. Hissom Drlg.Co.  
Issued. 12-6-41

County. Rooks



CASING:  
8 5/8" 148' Cem.  
5 1/2" 3130' Cem.

Elevation.

Production. Phy.Pot.177 B.  
No wtr

Figures Indicate Bottom of Formations.

surface rock	0-30
shale & shells	148
shale	480
sand	536
shale	630
sand	740
shale & shells	950
shale	1020
shale & sdy lime	1170
shale & shells	1635
shale	1660
lime sdy	1705
lime brkn	1767
shale & shells	1991
lime	2150
lime brkn	2274
lime	2350
shale & lime	2375
lime	2530
shale	2662
shale & lime shells	2680
shale	2838
lime	3075
shale & lime	3129
lime	3133
3133 Rot.TD = 3133 SLM	
lime	3183
3183 = 3182 SLM	
Total Depth.	

Top Lansing 3093  
Penetration 89

1 BOPH at 3177  
Good porosity & sat. 3179-82

3000 Gals.Acid 9-3-41  
5000 Gals.Acid 9-6-41  
3000 Gals.Acid 9-20-41