

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508E. Murdock, Wichita, Kansas


15-163-00200

Company - DUKE AND WOODS
Farm - Dunlap No. 1

SEC. 5 T. 9 R. 16W
NE NE NE

Total Depth. 3441
Comm. 6-15-49 Comp. 6-28-49
Shot or Treated.
Contractor.
Issued. 3-11-50

County. Rooks
KANSAS



CASING:
8 5/8" 175'

Elevation. 1984' m
1894'

Production. Dry

Figures Indicate Bottom of Formations.

clay, post rock	60
shale	154
shale, shells	175
shale	380
sand, shale	410
shale, lime	650
shale, shells	725
sand, shale	760
shale, shells	815
sand, shells	895
sand	950
red rock, shale	1140
red rock, shale, iron	1205
red rock, shale	1255
anhyd.	1290
red rock, shells	1310
anhydrite, shells	1320
red rock, iron, shale	1390
shale, shells	1435
iron, shale	1450
shale, red rock, iron	
strks	1490
shale, shells	1700
shale, shells, anhyd.	
brkn.	1765
shale, shells, anhyd.	1925
shale, shells	1950
lime, shale	2095
lime	2145
lime, shale	2290
lime	2403
lime, shale	2470
sand	2475
lime, shale	2880
lime	3000
lime, shale	3094
lime	3200
lime, shale	3370
lime brkn	3425
lime	3441
Total depth	

Tops:
Anhydrite 1255
Heebner 3042
Kansas City 3094
Arbuckle 3425