

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 E. Murdock, Wichita, Kansas


15-163-02975

Company - CITIES SERVICE OIL CO.
 Farm - Holy Cross No. 3
 (second hole)

SEC. 4 T. 9 R. 16W
 NE NE SE

355' S. & 330' W. of E/4
 County. Rooks corner

KANSAS



Total Depth. 3358 P.B. 3342
 Comm. 1-8-50 Comp. 1-19-50
 Shot or Treated. 4000 gals. 1-26-50
 Contractor. Lohmann-Johnson Drlg.
 Issued. 7-1-50

CASING:

8 5/8" 275' cem. w/150 sx.
 4 1/2" 3358' cem. w/175 sx.

Elevation. _____

Production. Pmp. 183 oil, 19 wtr
 24 hrs.

Figures Indicate Bottom of Formations.

shale & shells	640
shale & sand	910
sand	950
shale	1260
anhyd.	1295
shale	1307
shale & shells	1600
shale & lime	1800
lime brkn	1932
lime	2025
lime brkn.	2125
lime	2183
lime brkn	2681
lime	2710
lime brkn	2780
shale & lime	2850
lime	3069
lime & shale	3093
lime	3360
Total Depth 3360 = 3358 SLM	
P.B. 3342	

Tops: Corr.
 Heebner 3068
 Dodge 3087
 Lansing 3108

Pen. 250'

Drilled cement to 3342 SLM.

Perf. 33 shots 3326-34
 " 33 " 3232-40
 " 17 " 3195-99
 " 21 " 3179-84
 " 23 " 3168-74
 " 47 " 3150-62
 " 24 " 3120-26
 " 24 " 3110-16

1 gal. oil & 3 gals. wtr per hr.

Acid:
 500 gals. 3326-34
 500 gals. 3232-40
 2000 gals. 3150-99
 1000 gals. 3110-26