

6-9-16W

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

SIDE ONE

(Rules 82-3-130 and 82-3-107)

State Geological Survey

This form shall be filed with the Kansas ~~Wichita~~ ^{Wichita} ~~Commission~~ ^{BRANCH}, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.


F _____ Letter requesting confidentiality attached.

C ☒ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run _____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 8735 EXPIRATION DATE _____
OPERATOR S & M Oil API NO. 15-163-22,092
ADDRESS 205 North Jefferson COUNTY Rooks
Plainville, Kansas 67663 FIELD _____
** CONTACT PERSON George Crawford PROD. FORMATION Arbuckle
PHONE 913-885-4808
PURCHASER Farmland Industries, Inc. LEASE Kern
ADDRESS Kansas City, Mo. WELL NO. 1
WELL LOCATION 200' FSL; 400' FWL SW/
DRILLING Red Tiger Drilling Company 200 Ft. from South Line and
CONTRACTOR 1720 KSB Building 400 Ft. from West Line of (E)
ADDRESS Wichita, Kansas 67202 the SW (Qtr.) SEC 6 TWP 9S RGE 16W(W)
PLUGGING N/A
CONTRACTOR _____
ADDRESS _____
TOTAL DEPTH 3,460' PBDT _____
SPUD DATE 8/2/83 DATE COMPLETED 8/9/83
ELEV: GR 1978 DF 1980 KB 1983
DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.
DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING
USED TO DISPOSE OF WATER FROM THIS LEASE CR-98315

WELL PLAT



(Office Use Only)

KCC _____
KGS ☒

SWD/REP _____
PLG. _____

NGPA _____

Amount of surface pipe set and cemented 268.07 DV Tool Used? Yes

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion _____. Other completion _____. NGPA filing _____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

RECEIVED

NOV 2 1983

AFFIDAVIT

that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit.

CONSERVATION DIVISION
Wichita, Kansas

SIDE TWO
OPERATOR

S & M Oil Company

LEASE Kern

ACO-1 WELL HISTORY
SEC. 6 TWP. 9S RGE. 16W (W)

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
☒ Check if no Drill Stem Tests Run.				
☐ Check if samples sent to Geological Survey				
Surface Shale & Clay	0	281		
Shale & Sand	281	1015		
Shale & Red Bed	1015	1277		
Anhydrite	1277	1311		
Shale & Red Bed	1311	2230		
Shale	2230	2784		
Shale & Lime	2784	3030		
Shale & Lime Streaks	3030	3142		
Lime & Shale	3142	3229		
Lime	3229	3382		
Lime & Chert	3382	3443		
Lime	3443	3460		
RTD		3460		

State Geological Survey
WICHITA BRANCH

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used		Depth interval treated	
Date of first production 8-30-83	Producing method (flowing, pumping, gas lift, etc.)		Gravity
Estimated Production -I.P.	Oil 3.0 bbls.	Gas MCF 50 % 3.0 bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)		Perforations	

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	275'	Common	160	3% Gel. 2% C.C.
Production	7 7/8"	5 1/2"	14#	3,458'	Surefill	150	4# Gilsonite per
DV Tool					50/50 Pozmix	325	SX 6% Gel

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			