

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 E. Murdock      Wichita, Kansas

Company - BEN F. BRACK OIL CO., INC.  
Farm - McCartney      No. 1


SEC. 8      T. 9      R. 16W  
SW SE SE

15-103-02771

Total Depth. 3475; PB 3035  
Comm. 5-30-49      Comp. 6-13-49  
Shot or Treated. 2750 Acid  
Contractor.  
Issued. 10-21-50

County. Rooks

KANSAS



CASING:  
5 1/2" 3394' cem. w/125 sx

Elevation. 1967

Production. dry

Figures Indicate Bottom of Formations.

|                         |      |
|-------------------------|------|
| cellar                  | 5    |
| surface soil & shells   | 100  |
| shale & shells          | 200  |
| shale, redbed, shells   | 845  |
| shale & shells          | 975  |
| Anhydrite               | 1010 |
| shale & redbed          | 1200 |
| shale & shells          | 1255 |
| lime                    | 1300 |
| shale                   | 1330 |
| shale & lime            | 1930 |
| shale                   | 2100 |
| lime & shale            | 2625 |
| shale & lime streaks    | 2780 |
| lime & shale            | 2990 |
| lime                    | 3350 |
| lime & shale            | 3445 |
| Conglomerate & Arbuckle | 3475 |
| Total depth             |      |

|              |      |
|--------------|------|
| Tops: Scout  |      |
| Topoka       | 2868 |
| Lansing      | 3095 |
| Conglomerate | 3421 |
| Arbuckle     | 3448 |

Remarks:

Perf. 3334-38; 3324-28, 750  
acid; 35 GFPH, bld. 30 GFPH  
& 5 GOPH; PB 3315; Perf.  
3296-3302; 3276-81, 500 acid,  
65 GFPH; PB 3268; Perf. 3251-  
57; 3219-23, 1000 acid, 3 BFPH  
95% wtr; PB 3190; Perf. 3179-  
82; 3172-74; 3160-64; 3151-53;  
3139-42; 3118-30; PB 3155;  
Perf. 3095-3154; 500 gals. acid,  
wtr; PB 3035; Perf. 3040-46,  
water.