

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- **R.A. COMEAU & MURFIN DRILLING CO.**
 Farm- Smith "D" No. 1

SEC. 9 T. 9 R. 16W
 NE NW NE

15-163-01084

Total Depth. 3377'
 Comm. 5-15-63 Comp. 5-21-63
 Shot or Treated.
 Contractor. Murfin Drilling Co.
 Issued. 8-31-63

County Rocks
 KANSAS



CASING:
 8 5/8" 169' cem w/150 sx.

Elevation. 2009' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface hole	171
shale	490
sand	605
shale & sand	1000
redbed & shale	1273
Anhydrite	1309
shale-shells	1640
salt shale	1780
shale & lime	2125
lime-shale	2265
shale-lime	2891
lime & shale	3085
lime	3377 RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	1273
Base Anhydrite	1311
Topeka	2890
Heebner	3112
Toronto	3134
Lansing	3154

DST #1 3164-3230' Op 2 1/2 hr. Rec. 1600'
 wtr. IF 208#, FF 749#, ISIP 1119#/20"
 FSIP 794#/20"

DST #2 3240-73' Op 30". Rec. 10'
 drilling mud. IF 0#, FF 0#, ISIP 718#/
 20", FSIP 575#/20".