


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

T.C. JOHNSON
Fred Luhman No. 1

SEC. 10 T. 9 R. 16W.
CSL SE NW

Total Depth. 3220
Comm. 6-6-40 Comp. 6-29-40
Shot or Treated. 7000 gal acid.
Contractor. Walter Kuhn Drlg. Co.
Issued. 8-10-40

County Rocks.



CASING.

10" 43'10" Cem.
7" 3185' Cem.

Elevation.

Production. Pot. 2350 B.
Depthograph

Figures Indicate Bottom of Formations.

gravel	43
shale	174
shale and shells	720
Dakota sand	780
shale and sand	950
shale and shells	1585
red bed	1800
shale and shells	1825
broken lime	1834
anhydrite	1860
red rock and shale	1990
red rock	2000
anhydrite	2115
shale	2185
lime	2263
shale	2290
shale and shells	2340
shale and broken lime	2425
broken lime	2558
shale	2572
shale and shells	2783
shale	2880
lime	2902
broken lime	2977
shale	2996
lime	3009
broken lime	3120
shale	3125
lime	3146
broken lime & shale	3160
lime and shale	3178
broken lime and shale	3186 $\frac{1}{2}$
lime 150' OIH 3204	3219
shale blue	3220
Total Depth.	

SSO 3210-11
1100' OIH 3212-18
Acidized 7000 gal.