

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

15-163-30155

COMPANY CLINTON OIL

SEC. 11 T. 9 R. 16W

FARM Livingood

NO. 12 D

LOC. C NW

1300 FNL, 1250 FWL of NW¼

TOTAL DEPTH 3505'

COMM. 4-15-66

COMP. 4-24-66


SHOT OR TREATED

CONTRACTOR Garvey Drlg.

ISSUED 8-6-66

COUNTY Rocks

KANSAS



CASING

20	10	
15	8	5/8" 229' cem w/ 175 sx
12	6	
13	5	1/2" 3504' cem w/ 150 sx

ELEVATION 2032' KB

PRODUCTION 13.28 BOPD PLUS

60.52 EWPB (Lans 3181-3270)

FIGURES INDICATE BOTTOM OF FORMATIONS

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

95' Shale
624' Shale and Shells
670' Sand
1063' Red Bed and Shale
1262' Red Bed
1296' Anhydrite
1500' Shale
1850' Shale and Shells
2075' Shale and Lime
2355' Lime and Shale
2500' Shale
2615' Shale and Lime
3010' Lime and Shale
3391' Lime
3420' Lime and Shale
3605' Lime
3605' RTD

TOPS: SCOUT

Anhydrite	1260
Topeka	2886
Heebner	3110
Toronto	3140
Lansing	3156
Lansing B Zone	3193
" D "	3210
" F "	3232
" G "	3250
" H "	3298
" I "	3321
" J "	3339
" K "	3373
Base Kansas City	3418

State of Kansas

County of Barton

88