

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

15-163-01030
Sec. 11 T. 9 R. 16W.

Location SE c SW

Casing Record

20" 10"
15 1/4" 8 1/4"
12 1/2" 65/8"
12 1/2" 53/16"
Total Depth 3322'

Farm- Kruger et al No. 1
Company- Tatkenhorst et al.
Contr.-
Comm.- 11-8-27. Comp.- 9-5-1928.

County Rocks.



Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to

Elevation 2070

Initial Production 175 bbls.

Figures Indicate Bottom of Formations.
Date Issued. 9/29/1928.

Formation	Depth	Formation	Depth	Formation	Depth
soil	10	lime	1540	shale	2905
chalk	100	red rock	1550	lime	2925
shale	125	shale	1692	Show oil	
lime	180	lime	1695	shale	2958
shale	300	salt	1760	lime	2963
blue mud water	600	broken shale	1888	shale	2970
shale	603	lime	1912	lime	3000
sand	608	red rock	1950	black shale	3005
lime	618	shale	2025	Show oil	
shale	622	red rock	2055	lime	3045
sand water	632	lime	2085	sandy lime	3055
shale	635	red rock	2092	lime	3105
sand	660	lime	2125	shale	3110
shale	680	blue slate	2135	lime	3155
sand water	700	lime	2150	broken lime	3195
shale	730	shale	2162	lime	3205
red rock	750	red rock	2175	shale	3206
shale	780	lime	2198	lime	3211
red rock	785	red rock	2218	green & brown	
shale	790	lime	2245	shale	3220
red rock	800	shale drlg.	2250	lime	3224
shale	814	red rock	2258	blue shale	3228
sand	820	lime	2278	lime show oil	3232
shale	850	shale	2340	lime	3265
lime	855	lime	2350	lime shells	3270
shale	860	red rock	2390	600' oil 1 1/2 hr, 5 3/16	
sand water	882	lime	2400	at 3220'	
shale	890	lime	2425	lime	3290
shale	898	black shale	2430	well 50 bbls per	
lime	901	lime	2460	lime	3322
shale	930	blue shale	2469		
sand HFW	940	lime	2490	Total Depth	3322
shale	968	shale	2520		
sand	977	lime	2535		
dolomite	998	shale	2560		
water sand	1028	lime	2563		
red rock	1042	shale	2596		
iron	1045	brown shale	2602		
red rock	1125	blue shale	2646		
sand 1/4 BW	1133	lime	2660		
red rock	1180	shale	2720		
sand water	1230	blue shale	2755		
red rock	1290	lime	2760		
sand HFW	1300	white shale	2770		
sand	1310	grey shale	2785		
lime	1314	blue shale	2815		
red rock	1335	shale & lime 2BW	2825		
lime	1344	lime	2855		
red rock	1349	shale	2880		
lime	1376	lime	2886		
red rock	1515				