

SHINDHELM & HAYNES.
Dorr No. 1.

SEC. 13 T. 9 R. 16W.
Sec SW


15-163-03756

County. Rocks

Total Depth. 3614.
Comm. 6-14-38 Comp. 9-12-38
Shot or Treated.
Contractor.
Issued. 11-19-38

CASING

15 1/2" 676' 8 1/4" 2670 reamed to 2775
133/8" 990' 65/8" 2960'
10" 1286' 53/16" 3337' reamed to 3465
setting 90' 4" liner 3590



Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

clay	60	lime	2365	limo	3337
shale	605	shale and shells	2380	limo	3383
red rock	608	red rock caving.	2405	shalo	3385
sdv shale	620	lime	2435	limo	3407
5 BW 608-615		shale	2440	shalo	3410
red rock	645	lime	2460	limo	3420
shale grey	660	shale	2480	shalo brown	3423
red rock	670	lime	2495	limo	3455
red rock	680	shale	2510	oil show 3450-3455	
sand HFW	690	lime	2549	shalo	3460
shale	710	shale	2560	limo	3506
red rock	740	lime	2570	shalo blue caving	3515
sand	750	shale and shells	2590		
shale blue	765	lime	2605	limo	3526
shale blue caving	825	shale blue caving	2640	shalo	3542
shale blue caving.	900	lime	2665	limo	3575
sand	975	shale dark	2670	brokon limo and	
red rock	980	lime	2673	caving	3580
red rock	990	shale and shells	2705	cong.	3609
sand red	1140	lime	2715	granite vory hd.	3614
water LOBWFHR 1105-1140		shalo blue	2735	Total Depth.	
red rock	1250	lime	2740		
HFW 1225-1240		shale and shells	2765		
red rock	1275	lime	2770		
Correction 1275 equals	1283	shalo	2775		
anhydrite lime	1320-1800	lime	2787		
red rock	1365	shale blue	2825		
shale blue	1415	lime	2830		
red rock	1440	shale blue	2835		
lime shells & red rock	1500	lime	2845		
red rock	1530	shale blue	2855		
shale	1575	shalo blue	2870		
salt	1623	lime	2885		
lime	1815	shalo brown	2900		
lime shells	1855	lime	2914		
lime white	1865	shalo	2950		
shale	1890	lime	2955		
lime	1905	shalo	2972		
red rock	1945	lime	3020		
lime	1955	oil show	3020		
shale	1968	shalo	3025		
lime	2020	lime	3172		
shale	2025	shalo	3174		
red rock	2035	lime	3196		
lime grey	2065	shalo blk	3212		
red rock	2080	lime	3219		
lime white	2092	shalo blue	3223		
shale	2145	lime	3227		
red rock	2157	shalo	3232		
lime	2170	shalo brown	3235		
red rock	2205	lime	3237		
lime shells red rock	2235	shalo groen and			
lime	2257	brown	3250		
red rock	2270	lime	3270		
lime	2300	lime	3308		
lime broken	2305	show oil 3281-3285			
lime	2310	shalo blue	3311		
shale	2315	lime	3320		
red rock	2325	shalo	3327		