

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

15-163-03855

Location NW NW NE


(CORRECTED LOG)

Sec. 14 T.9 R. 16W.

Casing Record

County Rocks.

10" Farm- Blank No. 1
 20" 8 1/4" Company- Stearns-, Streeter Co.
 15 1/2" 65/8" Contr.-
 12 1/2" 53/16" Comm.- 4/23/1928. Comp.- 8/15/1928.
 Total Depth 3620' Shot Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Elevation 2079

Figures Indicate Bottom of Formations.

Initial Production Dry.

Date Issued. 1/11/30

Formation	Depth	Formation	Depth	Formation	Depth
sand yellow	76	shale blue	2230	shale blue	3190
slate blue	110	red rock	2240	lime white	3198
shale blue	125	lime white hrd	2250	shale red	3200
shale light.	180	red rock	2270	lime white	3206
shale blue	270	lime grey	2277	shale blue	3212
slate blue	505	red rock	2318	shale brown	3217
slate brown	595	lime grey	2343	shale green	3221
5 BW 595'		red rock	2410	Set 6 1/4" 3221'	
sand white	610	HFW at 2405'		Oswald lime	3241
shale light HFW	680	Set 10" csg. at 2410'		Depth corrected SL	
Set 15 1/2" csg. 698'		Depth corrected from 2390-		M. from 3221 to 3220'	
sand grey	699	2410'		Show Oil 3229 to 3235'	
slate grey	726	lime & sand	2420	slate	3246
slate pink	730	shale black	2425	lime	3294
sand grey	735	shale brown	2435	Show oil 3257 to 3262'	
red rock	745	lime white	2445	lime brkn	3314
slate blue	777	shale blue	2450	lime & slate	3335
red rock	810	UR 10"		4 BW 3335'	
sand light	818	slate blue	2458	lime	3375
shale blue	840	UR 10" from 2410-2441'		slate break	3378
3 BW at 810'		lime brkn	2505	lime	3385
Lowered 15 1/2" to 825'		lime white	2530	red rock	3389
slate blue	860	shale blue	2538	lime	3408
sand light	890	lime white	2572	slate	3418
HFW at 860'		slate blue	2615	lime	3448
slate blue	965	1 BW at 2570'		Set 5 3/16" csg. 3435'	
slate sandy blue	985	shale blue	2650	HFW 3440-3448'	
sand grey	1027	lime broken	2674	Depth corrected SLM	
red rock	1347	shale broken	2685	from 3436 to 3440'	
UR 15 1/2" from 825-1058'		shale blue	2717	break	3457
lime	1375	lime	2720	UR 5 3/16" from 3440-48'	
Set 12 1/2" csg. 1350'		shale blue	2756	Cleaning out & swabbing	
lime white hrd	1380	Set 8" csg. 2756'		lime	3469
red rock	1448	lime	2767	1/2 BW 3460 to 3465'	
slate blue	1480	slate blue	2780	lime brkn	3475
shale red	1575	sandy shale	2800	shale blue	3492
shale blue	1690	5 BW HR at 2795'		lime	3495
1/2 BW at 1655'		lime white	2824	shale blue	3505
salt brown	1790	HFW at 2810'		lime brkn	3520
salt brkn	1850	lime white	2827	red rock	3523
slate blue	1881	slate blue	2830	lime	3533
lime brown	1889	UR 8" from 2756 to 2820'		slate	3545
slate blue	1898	lime shells & slate	2845	lime shell	3546
red rock	1930	slate white	2877	shale pink	3553
shale blue	1950	lime grey	2882	UR 5 3/16" from 3448-	
red rock	1960	slate blue	2910	3542'	
lime white	1993	Bailing water		Cleaning out & swabbing	
slate blue	2005	shale blue	2960	Conglomerate	3593
red rock	2040	lime	3045	lime (Decorah)	3620
lime white hrd.	2060	Cement from 2820-2985'		Pulling 5 3/16" csg.	
shale blue	2065	shale	3060	Plugging back. to Oil Pay	
lime white	2100	lime	3100	HFW 3620'	
slate blue	2110	shale	3110	Total Depth	3620'
shale blue	2140	lime broken	3135		
red rock	2155	shale blue	3141		
lime white	2170	lime	3180		
slate blue	2176	1 BW 3148'			
red rock	2193	Oil show at 3142'			
lime grey	2215	lime white	3182		