

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-163-03613

Company - CITIES SERVICE OIL COMPANY
Farm - Dorr "B" No. 2

SEC. 17 T. 9 R. 16^W
SW NE SE
990' S & 990' W of E/4 corner

Total Depth. 3341' PB 3332'
Comm. 2-25-47 Comp. 3-6-47
Shot or Treated. Acid.
Contractor. R.W.Rine Drlg. Co.
Issued. 5-24-47

County. Rocks
KANSAS



Elevation. 2014 set

Production. Phy. Pot: 206 oil,
12% wtr, 24 hrs.

Figures Indicate Bottom of Formations.

soil & rock	0-60
shale	720
sand	935
shale & lime	1200
sand & shale	1450
shale & shells	1755
shale & lime	1935
shale & shells	2155
lime & shale	2230
lime	2390
lime & shale	2505
shale & shells	2765
lime & shale	2955
lime	3200
lime & chert	3275
lime	3342
RTD 3342=3341 SIM	
Total Depth	3341 SIM

Tops:
Lansing Corr. 3109
Penetration 232
Perf. Pen. Lansing-K.C. 221

Drilled cement to 3332 SIM.
Perf. 45 shots 3319 $\frac{1}{2}$ -3330 $\frac{1}{2}$
41 shots 3237 -48
12 shots 3231 -34
23 shots 3181 -88
10 shots 3158 -61
24 shots 3136 -42

250' oil and 2 bailers wtr, 12 hrs.
1050' oil in 48 hrs., 10 gals. wtr per hr.

3-15-47 Acidized 1000 gals. 3319 $\frac{1}{2}$ -30 $\frac{1}{2}$
" " 800 gals. 3231 -48
" " 1200 gals. 3136 -88