

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CITIES SERVICE OIL COMPANY
Farm - Dorr "B" No. 3

SEC. 17 T. 9 R. 16W
NE SW SE
990' N & 990' E of S $\frac{1}{4}$ corner

Total Depth. 3383' SIM

Comm. 3-29-47


Comp. 4-7-47

Shot or Treated. Acid.

Contractor. R. W. Rine Drilling Co.

Issued. 7-5-47

County. Rocks
KANSAS



Elevation. 2029 *scribble*

CASING:

8-5/8" 240' Cem. w/150 sx
5-1/2" 3383' Cem. w/150 sx

Production. Phy. Pot: 73 BO,
11% wtr, 24 hrs.

Figures Indicate Bottom of Formations.

surface hole	0-240
shale	685
sand	920
shale & lime	1205
shale & shells	1245
anhydrite	1285
shale & shells	2075
shale & lime	2125
shale & shells	2210
shale & lime	3030
lime	3110
lime & shale	3270
lime	3310
lime & shale	3379
3379 RTD = 3383 SIM	
Total Depth	3383 SIM

Tops:

Lansing Corr. 3134
Penetration 249

Drilled cement to 3353

Perf. 35 shots 3341-52

" 48 shots 3262-70

" 24 shots 3227-36

" 12 shots 3217-21

" 20 shots 3200-10

" 12 shots 3194-98

" 10 shots 3180-84

" 23 shots 3155-63

Bailed 50 gals. wtr and 9 gals.
oil per hour.

4-15-47 Acidized 1000 gals. 3341-52
" 1000 gals. 3155-63
" 1500 gals. 3255-70
" 1500 gals. 3180-3236