


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CIT ES SERVICE OIL CO.
Farm - Dorr "B" No. 4

SEC. 17 T. 9 R. 16W
NE NE SE
330' S, 330' W of
E/4corner
County. Rooks
KANSAS

Total Depth. 3330'
Comm. 7-20-48 Comp. 7-30-48
Shot or Treated. Acidized
Contractor. R. W. Rine Drlg. Co.
Issued. 10-16-48



CASING:
8 5/8" 244' Cem w/150 Sx.
4 1/2" 3327' Cem w/165 Sx.

Elevation. 1976 Ind
Physical Potential
Production. 168 Oil, 30% wtr, 24 hrs.

Figures Indicate Bottom of Formations.

clay, surface soil
15
post rock, lime 45
shale, clay 244
shale, shells 1215
anhydrite 1245
shale, shells 1760
lime, shale 1820
lime, brkn, shale 1985
lime, shale 2740
shale 2850
lime, shale 3075
lime 3330
total depth
3330 RTD = 3328 SLM

Schlumberger Electric log.

Corrected Tops:

Lansing 3077'
Penetration 251'
Perf. Lsg. K/C Pen. 239'.
Drilled cement to
3322 SLM.
Perf. 36 shots 3306-16
GSO.
Perf. 26 shots 3261-70,
GSO
Perf. 16 shotw 3245-49
Perf. 22 shots 3217-23.
Perf. 19 shots 3154-60.
Perf. 25 shots 3134-42.
Perf. 6 shots 3100-02.

80' fluid in 2 3/4 hrs.
Bailed 10 gals. oil and
7 gals water perhour for
7 hrs.

8-7-48 Acidized 1000 gals.
3606-16
8-9-48 Acidized 1500 gals.
3245-70
8-9-48 Acidized 1000 gals.
3217-23
8-11-48 Acidized 1000 gals.
3134-60
8-14-48 Pumped 234 oil,
81 wtr, 23 hrs.
8-15-48 Pumped 189 oil,
75 wtr. 24 hrs.