

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-163-00939

Company- CITIES SERVICE OIL
Farm- Dorr "D" No. 1

SEC. 17 T. 9 R. 16W
NE NE SW
330' S 330' W of Cen.

Total Depth. 3404' PB 3397'
Comm. 8-22-56 Comp. 9-1-56
Shot or Treated.
Contractor. Braden Drlg. Co.
Issued. 10-20-56

County Rooks,
KANSAS



Elevation. 2020' DF

Production. 44 oil, 31 wtr, 24 hrs.

CASING:

8 5/8" 245' w/175 sx cem.
5 1/2" 3404' w/175 sx cem.
DV-tool @ 1264' w/400 sx cem.

Figures indicate Bottom of Formations.

clay -sand-shale	245
shale-shells	740
sand-shale	1020
red bed-shale	1100
shale-shells	1240
anhydrite	1275
shale-shells	1765
lime-shale	2110
lime	3405

3405 RTD = 3404 SIM

Total Depth PB 3397

TOPS:

Corr. Topeka	2876
" Heebner	3097
" Dodge	3116
" Lansing	3135
" B/Kansas City	3390

Drilled cement to 3397 SIM

Perforating record 9-7-56

25 shots	3376-82
33 "	3349-57
29 "	3325-32
45 "	3298-3309
29 "	3277-84
17 "	3219-23
33 "	3205-13
21 "	3196-3201
45 "	3176-87
29 "	3145-52
21 "	3137-42
29 "	3114-21

Acidizing record

500 gals.	3376-82
1000 "	3349-57
750 "	3325-32
1250 "	3298-3309
750 "	3277-84
500 "	3219-23
1500 "	3196-3213
1250 "	3176-87
1250 "	3137-52
750 "	3114-21