

WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

15-163-03621

Company - C. W. TRICKETT ET AL
Farm - Daugherty No. 2

SEC. 18 T. 9 R. 16W
SW NW SW

Total Depth. 3400'

Comm. 12-8-46

Comp. 2-10-47


Shot or Treated. Acidized

Contractor. Sterling Drilling Co.

Issued. 3-29-47

County. Rooks

KANSAS



Elevation. 2040 *sd*

CASING:

8-5/8" 70' Cem. w/50 sx
5-1/2" 3400' Cem. w/100 sx

Production. 840 bbls. per day

Figures Indicate Bottom of Formations.

surface soil	0-70
shale	450
sand & shale	990
shale & shells	1285
anhydrite	1315
red bed & shells	1660
shale & lime	2100
lime	2300
shale & shells	2370
lime	2525
lime & shale	2950
lime	3400
Total Depth	

Perforations by Lane Wells Co.

1st Shot From 3368 to 3372-10 Holes-No Show

2nd	"	"	3372	"	3378	6	"	"	"
3rd	"	"	3356	"	3359	4	"	"	"
4th	"	"	3331	"	3335	4 & 12	"	"	"
5th	"	"	3324	"	3328	4	"	"	"
6th	"	"	3312	"	3315	4	"	"	"
7th	"	"	3302	"	3306	4	"	"	"

Acid. w/2000 gallon acid.

Set Lane Wells plug at 3288'

Perforated from 3216 to 3233, 33 holes

Perforated from 3194 to 3202, 22 holes

Acidized with 4000 gallon acid.