

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-03636


Company- CITIES SERVICE OIL CO.
Farm- Bessey No. 6

SEC. 21 T. 9 R. 16W
NE SW NW
1615' S 990' W NW cor.

Total Depth. 3413' PB 3406'
Comm. 11-2-56 Comp. 11-12-56
Shot or Treated.
Contractor. Braden Drlg. Co.
Issued. 12-22-56

County Rooks

KANSAS



Elevation. 2015' DF

Production. 412 BO, 73 wtr. 24 hrs.

CASING:

8 5/8" 240' w/175 sx cem.
5 1/2" 3412' 2/175 sx cem.

Figures indicate Bottom of Formations.

DV-tool @ 1267' w/400 sx cem.
& 200 cu ft. Stratacrete.

shale-shells	775
sand-shells	950
red bed-shale	1245
anhydrite	1280
shale-shells	1865
lime-shale	2060
lime	2500
lime-shale	2625
lime	3415

Total Depth PB 3406'
3415 RTD 1/2 3413 SLM

TOPS:

Corr. Topeka	2877
" Heebner	3099
" Dodge	3118
" Lansing	3142
" B/Kansas City	3398

Drilled cement to 3406' SLM

Perforating Record

25 shots 3385-91
33 shots 3357-65
33 shots 3331-39
49 shots 3309-21
37 shots 3282-91
37 shots 3262-71
33 shots 3245-53
24 shots 3237-43
24 shots 3197-3203
21 shots 3183-88
24 shots 3141-47
29 shots 3118-25

Acidizing Record

500 gals. 3385-91
750 " 3357-65
1000 " 3331-39
1250 " 3309-21
1000 " 3282-91
1000 " 3262-71
1500 " 3237-53
1250 " 3197-3203
500 " 3183-88
500 " 3141-47
750 " 3118-25