

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-03637

Company. CITIES SERVICE OIL CO.
Farm. Bessey No. 7

SEC. 21 T. 9 R. 16W
SW SE NW
330' N & 990' W of center

Total Depth. 3422 SLM PB 3411 SLM
Comm. 11-15-56 Comp. 11-25-56
Shot or Treated. Acid 850 gals 12-4-56
Contractor. Braden Drilling Co.
Issued. 3-2-57

County Rooks
KANSAS



CASING:
8 5/8" 240' cem w/17 sx.
5 1/2" 3421' cem w/175 sx.
DV-tool at 1304 w/100 sx.

Elevation. 2030 D.F.

Production. 77 Bls. oil + 9 BW

Figures indicate Bottom of Formations.

sand, shale	50
shale, shells	755
sand, shells	950
redbed, shale,	
shells	1270
anhydrite	1310
shale, s shells	1845
lime, shale	2000
lime	2525
lime, shale	2650
lime	3425
3425 R.T.D. = 3422 SLM	
Total Depth	
PB 3411 SLM	

Tops: Corr.
Anhydrite (Scout) 1270
Topeka 2888
Heebner 3111
Dodge 3130
Lansing 3152
Base Kansas City 3405

Perforating Record:

29 shots	3391-98
28 "	3337-47
49 "	3317-29
40 "	3290-3300
29 "	3254-61
25 "	3246-52
49 "	3202-14
21 "	3152-57
33 "	3128-37

Acidizing Record:

12-4-1956	
750 gals	3391-98
750 "	3364-71
1000 "	3337-47
1250 "	3317-29
1000 "	3290-3300
1250 "	3246-61
1250 "	3202-14
500 "	3152-57
1000 "	3128-37

7 7/8" Rotary hole.

Drilled cement to 3411 S.L.M.