


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- Bessey No. 8

15-163-03638
SEC. 21 T. 9 R. 16W
SW SW NW
330' N & 330' E of W/4 corner

Total Depth. 3434 S.L.M. PB 3424 S.L.M.
Comm. 12-11-56 Comp. 12-20-56
Shot or Treated.
Contractor. Braden Drilling Co.
Issued. 3-2-57

County Rooks
KANSAS



Elevation. 2037 D.F.

Production. 94 B.oil / 28 B.wtr.

CASING:

8 5/8" 243' cem w/175 sx.
5 1/2" 3433' cemw/175 sx.
DV-tool 1304 w/100 sx. well pack.

Figures Indicate Bottom of Formations.

sand, shale	50
shale, shells	715
sand, shale	950
shale, shells	1295
anhydrite	1325
shale, shells	1490
shale, lime	1795
shale, shells	1975
lime, shale	2125
lime	2455
lime, shale	2770
lime	3435
3435 R.T.D. = 3434 S.L.M.	

Total Depth
PB 3424 S.L.M.

Tops: Corr.
Topeak 2904
Heebner 3123
Dodge 3142
Lansing 3165
Base Kansas City 3416

Drilled cement to 3424 S.L.M.

Perforatind Record:

21	shots	3403-08
29	"	3376-83
32	"	3349-57
33	"	3329-37
29	"	3304-11
29	"	3283-90
25	"	3269-75
21	"	3261-66
17	"	3249-53
25	"	3233-39
17	"	3224-28
36	"	3206-15
13	"	3173-76
21	"	3163-68
29	"	3141-48

Acidizing Record:

12-28-1956		
500	gals.	3403-08
750	"	3376-83
1000	"	3349-57
1000	"	3329-37
750	"	3304-11
750	"	3283-90
1250	"	3261-75
500	"	3249-53
1000	"	3224-39
1000	"	3206-15
1000	"	3163-76
750	"	3141-48

7 7/8" Rotary hole.