

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-103-03639  
SEC. 21 T. 9 R. 16W  
NE SW NE

Company- PHILLIPS PETRO.  
Farm- Casey No. 1

Total Depth. 3471' PB 3345'  
Comm. 6-23-54 Comp. 8-10-54  
Shot or Treated.  
Contractor.  
Issued. 9-11-54

County Rooks

KANSAS



Elevation. 2073' D.F.

Production. 73 BO/9 BWPD fr Lansing Kansas City

CASING:

8" 248'  
5" 3470'

Figures indicate Bottom of Formations.

surface clay	25	& .56 BW.
sand	251	(9) Set plug 3282, perf.
sand-shale	605	3270-72
lime	1241	(10) 3264-68 w/24 shots, test-
sand-shale	2437	ed 1 hr. hole dry. Acid 500
shale-shells	2548	gals. last hour 2 Bo & 32. BW.
lime-shale	2942	Set plug 3260, Perf. Perf (11)
lime	3010	3242-50 w/32 shots, acid w/500
lime-shale	3135	gals. Last hr. test 3.09 BO & .52.
lime	3322	BW. Drove plug 3260 to 3275.
lime-chert	3360	(12) Set plug 3247 @ 3217-21
lime	3471 RTD	w/16 shots. Acid 500 gals.,
Total Depth PB	3354	bailed 1/2 gal. wtr. per hr. w/6
		gals. oil.
TOSS:		Drove plug @ 3237 to 3353. with
Howard	2939	final report 73 BO & 9 BW 24 hrs
Topeka	2966	fr 3344-50, 3302-12; 3270-72,
Heebner	3166	3264-68, 3264-68, 3242-50,
Toronto	3184	3217-21
Lansing Kansas City	3207	
Base Lansing Kansas City	3461	

(1) PBTD 3436, Perf. 3427-32, acid 500 & 1000, test. 0.24 BO & 1.21. BW.

(2) Plug 3402, Perf. 3282 3388-96. last hr. 14 gal. oil & 22 gal. wtr.

(3) Plug 3380 Perf. 32 shots 3368-76. Had communication with lower zone as acid wtr. was being recovered. Acid 500 gals. test 2-1/4 BO & 3/4 BW 6 hrs. Last hr. 17 gal. oil & 18 gal. wtr.

(4) PBTD 3354. Perf. 12 shots 3344-50, 1 1/2 hr. tested 13 gals. oil & 12 gals. wtr. SQUEEZE OFF ABOVE W/200 sx.

Drilled cement to 3420 & (5) Perf. 3391-98 w/38 shots last hr. tested 17 gal. oil & 12 gals. wtr.

Squeeze off with cement & drilled out cement to 3380 (6) Perf. 3368-76 w/32 shots tested 1/2 hr. rec. 1 gal. wtr. w/scum oil. Acid 500 gals. swab. 25 gal. wtr. w/scum oil in 4 hrs. pulled retained then swab 36 BW in swabbing dry.

(7) Set Baker Plug at 3360 Perf. 3344-50 w/24 acid 500 gals. last hr. 17 gals. oil & 3.7 BW in 8 hrs.

(8) Plug @ 3323, Perf. 2/40 shots 3302-12 rec. 2 gal. oil, acid 500 acid, last 3 hrs. 1.12 BO