

Operator
F & M Oil Co., Inc

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
dry hole

Well No. 1
S 33 T 9S R 16 W

Lease Name
Colohan

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

| FORMATION DESCRIPTION, CONTENTS, ETC. | TOP | BOTTOM | NAME | DEPTH |
|---|-----|--------|----------------------|--------------|
| DST #1 3176-92, 30-30-45-45. Weak blow. Rec. 65' S1.0CM. FP's 74-74, BHP's 159-140 Pipe strap okay. | | | Log Tops: Heebner | 3144 (-1101) |
| DST# 2 3198-3284, 30-30-45-45 Good Blow Rec. 110' mud 300' muddy water. FP's 56-262, BHP's 430-430 | | | Toronto | 3163 (-1120) |
| DST #3 3286-3300, 20-30-20-30. Weak 8 minute blow. Rec. 280' mud (S.O) FP's 177-177 BHP's 234-234#. | | | Lansing | 3187 (-1144) |
| DST #4 3327-3405, 30-30-45-45 Good blow throughout. Rec. 230' MW. FP's 84-116. BHP's 1100-1079. Temp. 107. Back in hole at 6:30' this morning and heading for Simpson. | | | Base KC | 3406 (-1366) |
| D & A | | | Cong. | 3451 (-1408) |
| | | | Simpson Sand | 3520 (-1477) |
| | | | Arbuckle | 3528 (-1485) |

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

| | |
|---------------|-----------|
| Date Received | Signature |
| | Title |
| | Date |

ELZbG