

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-163-01474

Company- BENNETT & ROBERTS OIL OPERATIONS
 Farm- Dunn "A" No. 1

SEC. 2 T. 9 R. 17W
 NW NW NE

Total Depth. 3450'

Comm. 4-2-62

Comp. 4-14-62


Shot or Treated.

Contractor.

Issued. 9-1-62

County Rocks

KANSAS



Elevation. 1966' DF

Production. 50 BOPD, NW

CASING:
 8 5/8" 235' cem w/160 sx.
 5 1/2" 3449 1/2' cem w/175 sx.

Figures Indicate Bottom of Formations.

surface clay & rock	40
shale & shells	520
shale & sand streaks	650
shale	840
sand	1030
red bed	1278
anhydrite	1310
shale & shells	1740
shale & streaks of lime	1975
shale & lime	3425
lime	3450

DST #8 3306-3342' op 1 hr. w/very weak
 blow for 9 min. Rec. 9' very slight oil
 cut mud. IBHP 870# FBHP 95# IFP 0#
 FFP 0#.

Total Depth

TOPS: SAMPLE

Topeka Lime	2852
Heebner Shale	3068
Toronto Lime	3088
Lansing Kansas City	3109
Base Kansas City	3350
Conglomerate Chert	3412
Arbuckle Dolomite	3425

DST #1 3009-3050' op 1 hr. w/fair blow
 throughout. Rec. 90' gas, 30' HO & GCM,
 150' VHO & GCM, & 30' salt water, IBHP
 1195#, FBHP 1077#/30 min. IFP 65#
 FFP 170#.

DST #2 3075-3095' op 1 hr, w/strong
 blow thruout. Rec. 60' gas, 60' HO &
 GCM, 60' muddy, gassy oil, & 240' clean
 gassy oil. IBHP 1212#/30 min, FBHP
 1085#/30 min. IFP 50# FFP 140#.

DST #3 3098-3120 op 1 hr, w/weak steady
 blow thruout. Rec. 60' gas, 60' HOCM.
 IBHP 1000#/30 min. FBHP 933#/30 min.
 IFP 0# FFP 0#.

DST #4 3134-3160 op 1 hr. w/weak blow
 for 1 hr, Rec. 70' watery mud w/slight
 show oil. IBHP 1150#/30 min. FBHP 980#/
 30 min. IFP 45# FFP 95#.

DST #5 3176-3205' op 1 hr. w/strong blow
 thruout. Rec. 1890' gas, 30' O & GCM,
 540' gassy & slightly mud cut oil. IBHP
 950#/30 min. FBHP 770#/30 min. IFP 100#
 FFP 215#.

DST #6 3207-3218' op 1 hr. w/strong blow
 thruout. Rec. 90' gas, 30' O & GCM, 120'
 O & GC Mdy salt water. IBHP 625#/30 min.
 FBHP 590#/30 min. IFP 0# FFP 200#.

DST #7 3267-3305' op 1 hr. w/strong blow
 thruout. Rec. 590' gas, 370' slightly
 muddy, gassy oil. IBHP 1072#/30 min.
 FBHP 940#/30 min. IFP 95# FFP 180#.