

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-163-02835

Company- BENNETT & ROBERTS OIL OPERATIONS
Farm- Howat No. 2

SEC. 2 T. 9 R. 17W
NW NE SE

Total Depth. 3390'

Comm. 11-23-62


Comp. 12-5-62

Shot or Treated.

Contractor.

Issued. 2-9-63

County Rooks
KANSAS



CASING:

8 5/8" 233' cem w/160 sx.

Elevation. 1989' DF

Production. DRY

Figures Indicate Bottom of Formations.

clay	20
rock & clay	30
shale & shells	233
shale	520
sand	575
shale	880
sand	995
red bed	1268
anhydrite	1305
shale & shells	1415
shale	1759
shale & lime	2895
lime	2975
lime & shale	3070
lime	3390 RTD
Total Depth	

TOPS:

Topeka Lime	2880
Heebner Shale	3096
Toronto Lime	3117
Lansing-Kansas City	3137
Base Kansas City	3380

DST #1 3290-3360' Tool op 1 hr. w/weak
steady blow thruout test. Rec. 120' drilling
mud. IBHP 960psi/30 min. FBHP 590psi/30 min.
FP's ranged from 0 to 130 psi.