

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-01480

Company- BENNETT & ROBERTS OIL OPERATIONS
Farm- Traynor No. 4

SEC. 2 T. 9 R. 17W
NW SE NE

Total Depth. 3375'
Comm. 11-20-63 Comp. 11-28-63
Shot or Treated.
Contractor. Bennett & Roberts Drig.
Issued. 3-21-64

County Rooks
KANSAS



CASING:
8 5/8" 244' cem w/160 sx.
5 1/2" 3374 1/2' cem w/200 sx.

Elevation. 1965' KB

Production. 37 BOPD, 35% WTR.

Figures Indicate Bottom of Formations.

post rock & surface soil	40
shale	830
shale & sand	975
redbed & shale	1175
redbed & shale	1269
Anhydrite	1307
shale & shells	1800
shale & lime	2910
lime	3375 RTD
Total Depth	

TOPS:	<u>SAMPLE</u>	<u>LANE-WELLS</u>
Topeka	2852	2853
Heebner	3069	3069
Toronto	3089	3089
Lansing Kansas City	3110	3110
Base Kansas City	3355	Not on log

DST #1 3206-26' 90' zone only. Op 1 hr,
initial shut in 30". Final shut in 30".
Very weak blow for 1 hr. Rec. 115" heavily
oil & gas cut mud. IBHP 285, FBHP 260, IFP
65, FFP 90.

DST #2 3262-3306' (160' & 180" zones)
Op 45". Initial shut in 30". Final shut
in 30". Very weak blow for 35". Flushed
anchor twice. Rec. 20' oil & gas cut mud
& 45' slightly oil & gas cut mud. IBHP
380, FBHP 210, IFP 0, FFP 130.

DST #3 3306-38' (210' zone) Op 30".
Final shut in 30". Very weak blow for 4".
Rec. 7' mud. FBHP 125, IFP 0, FFP 0.