


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING CO.
Farm- Fike "A" No. 3

15-163-71099
SEC. 5 T. 9 R. 17W
SW NW SE

Total Depth. 3461
Comm. 6-16-55 Comp. 8-1-55
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 1-28-56

County Rocks
KANSAS



Elevation. 2013 RB

Production. 36 BOPD

CASING:
8 5/8 162' w/ 125 sx cmt.
5 1/2 3450' w/ 75 sx cmt.

Figures indicate Bottom of Formations.

shale	135
shale & shells	535
sand	595
shale & shells	700
shale & sand	920
sand	1018
shale & shells	1084
red bed & shale	1333
anhydrite	1370
shale & shells	1690
salt & shale	1765
shale, lime & shells	2090
shale & lime	3266
lime	3275
lime & shale	3461
Total Depth	

TOPS:	
Topeka	2900
Heebner	3120
Toronto	3139
Lansing-K. C.	3157
Base K. C.	3379
Conglomerate	3430
Arbuckle	3447

DST #1: 3157-99, open 1 hr. wk. bl.
rec. 60' OC muddy SW, BHP 0#

DST #2: 3212-41, open 1 hr. rec. 10'
mud, BHP 0#

DST #3: 3240-66, open 1 hr. rec. 30'
mud, BHP 0#

DST #4: 3318-38, open 1 hr. rec. 12'
mud, BHP 400#