


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- MURFIN DRILLING CO.  
 Farm- Mainquist "C" No. 3

SEC. 9 T. 9 R-17W  
 NE SW NE

Total Depth. 3508'  
 Comm. 6-18-62 Comp. 6-25-62  
 Shot or Treated.  
 Contractor.  
 Issued. 1-19-63

County Rooks KANSAS



**CASING:**  
 8 5/8" 185' cem w/135 sx.  
 5 1/2" 3505' cem w/125 sx.

Elevation. 2085' KB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

shale	100
shale & shells	800
sand & shale	1120
shale & red bed	1390
red bed + shale	1411
Anhydrite	1449
shale & shells	1785
salt - shale	1875
shale - lime shells	2100
shale & lime	2320
lime & shale	2720
shale - lime	3040
lime - shale	3285
lime	3410
lime & shale	3480
lime	3508 RTD
Total Depth	

<b>TOPS: ELECTRIC</b>	
Anhydrite (scout)	1411
Topeka	2968
Heebner	3190
Lansing	3230
Sandstone	3464
Arbuckle	3502

DST #1 3314-3340', op 1 hr, strong blow,  
 Rec. 60' gas, 60' gas & oil cut mud,  
 60' oil cut mud, 240' heavily oil cut  
 mud, 240' water. IF 7#, FF 329#, IBHP  
 1100#/30 min., FBHP 703#/30 min.

DST #2 3312-3326', op 1hr, strong blow,  
 Rec. 530' gas, 100' heavily oil cut mud,  
 245' oil, 35' water. IF 7#, FF 145#,  
 IBHP 732#/30 min, FBHP 681#/30 min.

DST #3 3464-3485', op 1 hr. Dead. Rec.  
 10' mud. IF 4#, FF 7#, IBHP 723#/30 min,  
 FBHP 645#/30 min.