

MAY 1 1971

DRILLERS LOG

P 26 BOPD + tr. into
man. sd

COMPANY:
CONTRACTOR:
LEASE NAME:
LOCATION:

Rosen Oil Corporation
Aspen Drilling Co.
Carmichael #1
NW SW NE Sec. 10-T9S-R17W
Rooks County, Kansas
2017' K.B.
14 jts. (286') 8 5/8"
101 jts. (3470') 5 1/2"
January 30, 1971
February 10, 1971
3458'

ELEVATION:
SURFACE CASING:
OIL STRING:
COMMENCED:
COMPLETED:
ROTARY TOTAL DEPTH

FORMATION DEPTH

Clay & Post Rock	35
Post Rock	60
Sand Shale	150
Shale	315
Shale & Sand	1015
Red Bed & Shale	1085
Shale & Red Bed	1306
Anhydrite	1345
Shale & Shells	1588
Shale & Lime	2105
Lime & Shale	2761
Shale & Lime	3010
Lime	3127
Heebner	3130
Lime	3425
Lime & Shale	3454
Arbuckle	3458

Ran 14 jts. (286') 8 5/8" casing
set at 293' with 175 sacks cement.
Cement did circulate.

DST #1	3152-3225
DST #2	3248-3275
DST #3	3306-3340
DST #4	3340-3385
DST #5	3394-3425

Ran 101 jts. (3470') 5 1/2" casing
set at 3455' w/100 sacks cement.

Log Joffe	
* anhydrite	1306
B. "	1345
B. "	3124
Heebner	3167
L.K.C.	3406
B. man. sd.	3411
B. " "	3454
Arbuckle	3454

AFFIDAVIT

* Sample Joffe

State of Kansas)
) SS:
County of Barton)

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
William S. Schachle, Affiant

Subscribed and sworn to before me this 11th day of February, 1971.

Debra Johnson

