

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-163-30208

COMPANY OKMAR OIL

SEC. 10 T. 9 R. 17W
 LOC. SE SE NW

FARM Flegg

NO. 1

TOTAL DEPTH 3474

COMM. 8-7-66

COMP. 8-14-66


SHOT OR TREATED

CONTRACTOR Lehen Drlg.

ISSUED 11-5-66

COUNTY Rooks

KANSAS



CASING

20	10	
15	8 5/8"	@ 208' w/160 SX.
12	6	
13	5 1/2"	@ 3473'

ELEVATION 2033' KB

PRODUCTION PMP 52 BOPD &
 3 % Wtr. (Basal Penn
 3419-22) GR 36.2

FIGURES INDICATE BOTTOM OF FORMATIONS

0	40	Surface Soil, Post Rock
40	760	Shale
760	1025	Sand, Shale
1025	1317	Redbed
1317	1354	Anhydrite
1354	1775	Shale
1775	3060	Lime, Shale
3060	3440	Lime
3440	3473	Conglomerate
	3473	RTD - Set 5 1/2" Casing

Set 8 5/8" 8 rd. 24# used surface casing @ 208' with 160 sacks
 Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is
 a true and correct copy of the log of the Flegg #1 Well, located
 SE SE NW of Section 10, Township 9 South, Range 17 West, Rooks County,
 Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

TOPS: SCOUT

Anhydrite	1317
Heebner	3140
Toronto	3161
Lansing	3180
Base Kansas City	3414
Penn Sand	3418-37
Arbuckle	3466