

COMPANY **OIL PROPERTY MANAGEMENT**

SEC. 10 T. 9 R. 17W
LOC. NW NW SE

FARM Oswald

NO. 3

15-163-30235

TOTAL DEPTH 3479

COMM. 12-12-66

COMP. 12-19-66


SHOT OR TREATED

CONTRACTOR D & D Drlg.

ISSUED 3-11-67

COUNTY **Rooks**

KANSAS



CASING

20	10		
15	8 5/8"	@ 77'	w/75 SX
12	6		
13	8 1/2"	@ 3470'	w/200 SX

ELEVATION 2031' KB

PRODUCTION PMP 25 BOPD/NW
(MAR Sd 3417-23)

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale	760'
Shale and Sand	1303'
Anhydrite	1340'
Shale	1775'
Shale and Lime	2417'
Shale	2530'
Shale and Lime	3005'
Lime	3479'
Rotary Total Depth	3479'

Ran 2 jts. 8-5/8" surface pipe at 77'. Cemented w/75 sx. HA5

Set 4 1/2" casing @ 3470', 9' off bottom, w/200 sx. sat. salt pozmix, 3/4% CER2.

A F F I D A V I T

State of Kansas)
) SS:

TOPS: SCOUT

Anhydrite	1302
B/Anhydrite	1337
Heebner	3136
Toronto	3161
Lansing	3180
B/Kansas City	3413
Marmaton Sand	3417
B/Marmaton Sand	3423
*Arbuckle	3466

* SAMPLE TOP