

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas

Company DELTA & HARBAR DRILLING CO.
Farm Westhusin "A" No. -1


SEC. 11

15-163-71132
T. 9
NW NE SE

Total Depth. 3414
Comm. 6-4-48
Shot or Treated.
Contractor.
Issued. 4-15-50

Comp. 7-21-48

County. Rooks
KANSAS



CASING:
10 3/4" 102' cem w/100 sx
5 1/2" 3408' cem w/100 sx

Elevation. 2004 ft

Production. 954 bbls.

Figures Indicate Bottom of Formations.

clay & shale	40
shale & shells	55
sand	70
shale & shells	505
sand	570
shale, shells & salt	1045
shale & redbed	1255
anhydrite	1295
shale & redbed	1745
anhydrite	1795
shale & shells	1885
shale & lime	2170
lime	2260
lime & shale	2840
lime	3414
Total depth	

Tops:

Topeka	2875
Hoebner	3090
Toronto	3112
Lansing	3130
B. K.C.	3323
Arbuckle	3408