


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

JOHN H. LEAVELL
Box No. 1.

15-163-04004
SEC. 12 T. 9 R. 17W
SWc NW
330'E 330'N SWcNW $\frac{1}{4}$

Total Depth. 3255'
Comm. 5-17-37 Comp. 6-24-37
Shot or Treated. 3000 Gals.
Contractor. Mid-Union Drlg. Co.
Issued. 1-1-38

County. Rocks



CASING:

12 $\frac{1}{2}$ " 124'
8 $\frac{1}{2}$ " 3161'

Elevation.

Production. Pot. 1084 B.

Figures Indicate Bottom of Formations.

surface sand	125
lime	175
shale	300
shale w/ shells	495
sand	550
shale	590
shale w/ lime shells	873
red shale w/ sand	1130
shale	1240
lime	1305
shale	1340
shale w/ lime strks	1587
salt strk	1616
shale	1760
brkn lime	1992
lime w/ shale strks	2188
shale	2256
shale & lime strks	2326
lime brkn	2380
shale	2427
lime	2481
lime w/ shale strks	2757
shale	2894
shale w/ lime strks	2911
lime brkn	2920
lime	3165
lime white hrd	3235
Cable Tool Drlg.	
lime sft	3238
lime white hrd	3245
lime	3255
Total Depth.	

Deepening Rcd:

Comm. 2-4-42

Comp. 2-18-42

Prod.: Pot. 575 bbls.;

1m. 3255-3318 T.D.

Hole filled 850' from 3207-3216

Hole filled 2650' from 3235-3245

Swabbed 5 B. before acidizing from 3235-45

Potential test 1074 bbls(24 hrs)

Potential test 1084 bbls (8hrs)

Top Topeka lime 2895

Top Kansas City 3146