


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - ATLANTIC REFG. CO.
Farm - McClay No. 3

15-163-01503
SEC. 12 T. 9 R. 17W
SE NW SW

Total Depth. 3435' D.F.
Comm. 10-5-48 Comp. 11-5-48
Shot or Treated. Acidized.
Contractor. South Oak Drlg. Co.
Issued. 1-1-49

County. Rooks
KANSAS



CASING:
10-3/4" 179' Cem. W/150 Sx.
5-1/2" 3432' D.F. Cem. W/200 Sx.

Elevation. 2030' Ind.

Production. 150 Pot., Minimum
well, 25 BOPD

Figures Indicate Bottom of Formations.

surface clay	190
shale & shells	1290
anhydrite	1335
shale & shells	2085
lime	2215
lime & shale	2375
shale & shells	2510
lime	2555
shale	2685
shale & shells	2940
lime	3035
lime brkn	3078
lime	3435
Total Depth D.F.	

Tops, D.F.:
Hoebner 3117
Toronto 3136
Lansing 3158
Arbuckle 3431

Producing area: 3432-3435

State productivity test
taken 12-2-48, 150 potential,
Minimum well, 25 BOPD effective
11-5-48

Set 5 1/2" casg at 3432' DF w/200 sx.
sulphate resistant ce. at TD of 3433
(DF). Drilled plug. Swabbed down.
7 hr static 800' oil. Put in 1 barrel
acid. tested 140 gals. oil per hr.
Deepened 2' 3435' (DF). No increase in
fluid. Acidized w/500 gals. Pumped
222 bbls. fluid in 24 hrs, showed
15 to 60% salt wtr.