

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


15-163-01504

Company - ATLANTIC REFG. CO.
Farm - Mc Clay No. 4

SEC. 12 T. 9 R. 17W
NW NW SW
100' S of Center of NW NW SW
of 12-9-17W.
County. Rooks

Total Depth. 3436' D. F.
Comm. 11-8-48 Comp. 11-27-48
Shot or Treated. Acidized
Contractor. South Oak Drlg. Co.
Issued. 2-5-49

KANSAS



Elevation. 2036 Ind.

Production. 341 BO & no wtr.

Figures Indicate Bottom of Formations.

shale & shells	50
shale & sand	80
shale & shells	202
shale & sand	560
water sand	580
lime & shale	620
shale & sand	860
shale & shells	1190
shale & red bed	1285
anhydrite	1350
shale & shells	1650
shale & salt	1720
shale & shells	1915
lime & shale	2000
lime	2030
lime brkn	2200
lime	2520
shale & shells	2910
lime brkn	2980
lime	3060
lime brkn	3148
lime	3436 D.F.
Total Depth	

Top Arbuckle 3432 D.F.

Acid. W/1 barrle, 40 bbls.
fresh wtr. Cleaned out.

Perforated open hole 3432 $\frac{1}{2}$ to 3435 $\frac{1}{2}$
No increase.

Jetted 3432 $\frac{1}{2}$ to 3435 $\frac{1}{2}$ W/about 3000
gals. of 4 to 5% acid, down tubing
Formation took acid on vacume.
Cleaned up acid water.

Swabbed 10 to 15 BOPH, no wtr.

State productivity test, 12-22-48:
341 bbls. oil, no water.

Daily Allowable: 25 BOPD effective 12-2-48