

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

15-103-00009

Company- DAVIS BROTHERS
 Farm- Rempe "A"

No. 1

SEC. 28 T. 9 R. 17W
 C NW SW

Total Depth. 3620'
 Comm. 4-24-62

Comp. 5-3-62


County Rooks

KANSAS

Shot or Treated.

Contractor. Woodman & Iannitti Drilling Co.

Issued. 9-1-62



CASING:
 8 5/8" 155' cem w/130 sx.
 4 1/2" 3619' cem w/275 sx.

Elevation. 2120' RB

Production. 135 BOPD

Figures Indicate Bottom of Formations.

clay	35
sand	60
clay	130
blue shale	155
shale	640
shale & streak of sand	985
sand	1150
red bed	1415
Anhydrite	1450
shale & shells	2050
lime & shale	2210
lime	2735
lime & shale	2885
lime	2960
shale & lime	3080
lime	3497
conglomerate	3542
simpson dolomite	3596
arbuckle dolomite	3616
Total Depth	3620

TOPS: SAMPLE

"A" Zone	3279 - 3307
"B" Zone	3315 - 3332
"D" Zone	3335 - 3350
"E" "F" & "G" Zones	3360 - 3405
"H" Zone	3415 - 3430
"I" Zone	3440 - 3456
"J" Zone	3458
"K" Zone	3483 - 3498
"L" Zone	3500 - 3514
Marmaton	3528 - 3542

TOPS: LOG

Topeka	3023
Heebner	3237
Toronto	3260
Lansing	3281
Base Kansas City	3514
Conglomerate	3539
Simpson Dolomite	3596
	3616