


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock. Wichita, Kansas

Company- REPUBLIC DRILLING
Farm- Watkins No. 1

15-163-30332
SEC. 28 T. 9 R. 17W
C S $\frac{1}{2}$ SW NW

Total Depth. 3670'
Comm. 5-16-65 Comp. 5-25-65
Shot or Treated.
Contractor. Transit Corp.
Issued. 9-25-65

County Rooks
KANSAS



CASING:

Elevation. 2117' KB

8 5/8" 186' cem w/ 140 sx

Production. DRY

Figures Indicate Bottom of Formations.

surface soil	40
sand	50
shells	120
sand	130
shale	186
shale & shells	965
sand	1150
shale	1416
anhydrite	1456
shale, shells & red bed	1880
shale & shells	1960
shale & lime	2055
lime w/shale	2230
lime & shale	2325
shale w/lime strks	2390
lime & shale	3035
lime	3175
lime & shale	3245
lime	3610
lime & chert	3620
Arbuckle	3670
Total Depth	

TOPS: SMP

Topeka	3028
Heebner	3243
Toronto	3265
Lansing	3285
Base Kansas City	3515
Cherty Conglomerate	3538
Simpson	3576
Arbuckle	3620